(MULTIPLE BUILDING LOCATIONS)

SUBMITTED FOR: CONSTRUCTION JULY 29, 2022

OWNER:

GREENVILLE COUNTY SCHOOLS 301 E. CAMPERDOWN WAY GREENVILLE, SC 29601

ARCHITECT:

CRAIG GAULDEN DAVIS, INC. 19 WASHINGTON PARK GREENVILLE, SOUTH CAROLINA 29601

CIVIL ENGINEER: WK DICKSON

1329 MAIN STREET, SUITE 400 COLUMBIA, SC 29201

DRAWING LIST

T100 TITLE SHEET

CIVIL	
C100	GENERAL NOTES
C101	DEMOLITION PLAI
G102	DEMOLITION PLAI
G103	DEMOLITION PLAI
C104	SITE PLAN
C105	DETAILS

SUMMARY OF PROJECT SCOPE

PROJECT SCOPE CONSISTS OF BUILDING DEMOLITION AT THREE LOCATIONS: 1. EAST GANTT ELEMENTARY

2. WADE HAMPTON ELEMENTARY

THE SCOPE OF WORK FOR EACH LOCATION INCLUDES THE FOLLOWING:

2. BUILDING DEMOLITION. DEMOLISH EXISTING BUILINDGS, INCLUDING ASSOCIATED SLABS, FOOTINGS, AND RETAINING STRUTURES. TERMINATE AND CAP UTILITIES. DISPOSE OF ALL DEMOLISHED MATERIAL OFF SITE. SEE DRAWINGS AND SPECIFICATIONS FOR ADDITIONAL INFORMATION.

3. SITE REPAIR AND STABILIZATION. GRADE AND PREPARE SITE FOR STABILIZATION AND GRASSING. CLEAN AND RESTORE PORTIONS OF THE SITE THAT WERE DISTURBED FROM DEMOLITION ACTIVITY. INSTALL WALKWAYS OR PAVING WHERE SHOWN ON THE DRAWINGS

ALTERNATES


ALTERNATE 01: DEMOLISH AND DISPOSE OF 44 EXISTING PORTABLE CLASSROOMS CURRENTLY STORED AT THE EAST GANTT ELEMENTARY SCHOOL LOCATION. OWNER WILL IDENTIFY THE UNITS TO BE REMOVED PRIOR TO COMMENCEMENT OF WORK. BELOW IS QUANTITY AND SIZE INFORMATION FOR

a. 43 PORTABLE CLASSROOM UNITS AT 24' x 36' EACH b. 1 PORTABLE CLASSROOM UNIT AT 24' x 60'

NOTE: PORTABLE CLASRROM BUILDINGS ARE IN A STATE OF STORAGE AND ARE NOT CONNECTED TO UTILITIES.

ALTERNATE 02: MODIFY DEMOLITION REQUIRMENTS FOR THE EAST GANTT ELELMENTARY SCHOOL AS FOLLOWS: a. DEMOLISH THE EXISTING BUILDING TO TOP OF FLOOR SLAB. FLOOR SLAB AND BELOW GRADE BUILDING ELEMENTS TO REMAIN IN PLACE. b. CUT STURCTURAL. PLUMING AND UTILITY PENETRATIONS FLUSH WITH TOP OF SLAB AND FILL OPENINGS WITH NON-SHRINK GROUT.

NOTE: REMAINDER OF THE PROJECT SCOPE INCUDING HAZARDOUS MATERIAL REMOVAL, WASTE DISPOSAL, AND SITE STABILIZATION SHALL BE IN ACCORDANC WITH THE BID DOCUMENTS.







1 East Gantt Elementary Vicinity Map

T100 NOT TO SCALE Wade Hampton Elementary Vicinity Map
NOT TO SCALE

3 Old Southside High Gym Vicinity Map

NOT TO SCALE

Architecture Planning Interiors

Greenville, SC 29601 Phone 864.242.0761

19 Washington Park

E-mail cgd@cgdarch.com

COPYRIGHT © 2022 CRAIG GAULDEN & DAVIS, INC ALL RIGHTS RESERVED

THE ARCHITECT AND MUST BE RETURNED

CONSULTANT

GREENVILLE COUNTY SCHOOLS

BUILDING DEMOLITION PACKAGE

301 E. CAMPERDOWN WAY, GREENVILLE, SC 2960

MULTIPLE BUILDING LOCATIONS

Construction Documents DATE: 07/29/2022 PROJECT NO: 22030

CHECKED BY: TITLE SHEET

DRAWN BY:

T100

5-FOOT CONTOUR

1-FOOT CONTOUR

SPOT ELEVATION

STORM DRAINAGE PIPE

STORM DRAINAGE STRUCTURE

LIGHT POLE

TRANSFORMER

UNDERGROUND GAS LINE

SY

GAS VALVE

OHE

OVERHEAD UTILITY LINE

UNDERGROUND POWER LINE

UNDERGROUND TELEPHONE/CABLE LINE

UNDERGROUND FIBER OPTIC LINE

__ <u>18" RCP</u> __

— — — BB — — — — BB — — —

DI CB

UNDERGROUND FIBER OPTIC LINE

① TELEPHONE MANHOLE

POWER MANHOLE

IRRIGATION LINE

WATER LINE

WATER VALVE

WATER METER

WELL

FIRE HYDRANT

TOP OF BANK

PROPERTY LINE

ROADWAY CENTERLINE

LIMITS OF DISTURBANCE

STORM DRAINAGE REMOVAL

CONCRETE CURB AND GUTTER REMOVAL

BOTTOM OF BANK

PAVEMENT REMOVAL

ASPHALT PAVEMENT

CONCRETE SIDEWALK

EROSION CONTROL MATTING

COMPOST FILTER SOCK CHECK DAM

COMPOST FILTER SOCK

SEDIMENT TUBE INLET PROTECTION

SURFACE DRAINAGE FLOW DIRECTION

SILT FENCE

DOUBLE ROW SILT FENCE

DIVERSION BERM

(-0-

____ W ____

 \bowtie

ENGINEER:

WK DICKSON
CONTACT: CLAY CANNON, P.E., LEED AP,
SENIOR CIVIL CONSULTANT
1320 MAIN STREET, SUITE 400
COLUMBIA, SC 29201
803-786-4261 (PHONE)
CCANNON@WKDICKSON.COM (EMAIL)

WWW.WKDICKSON.COM

SCDHEC EROSION AND SEDIMENT CONTROL NOTES:

- IF NECESSARY, SLOPES, WHICH EXCEED EIGHT (8) VERTICAL FEET SHOULD BE STABILIZED WITH SYNTHETIC OR VEGETATIVE MATS, IN ADDITION TO HYDROSEEDING. IT MAY BE NECESSARY TO INSTALL TEMPORARY SLOPE DRAINS DURING CONSTRUCTION. TEMPORARY BERMS MAY BE NEEDED UNTIL THE SLOPE IS BROUGHT TO GRADE.
- 2. STABILIZATION MEASURES SHALL BE INITIATED AS SOON AS PRACTICABLE IN PORTIONS OF THE SITE WHERE CONSTRUCTION ACTIVITIES HAVE TEMPORARILY OR PERMANENTLY CEASED, BUT IN NO CASE MORE THAN FOURTEEN (14) DAYS AFTER WORK HAS CEASED, EXCEPT AS STATED BELOW:
- A. WHERE STABILIZATION BY THE 14TH DAY IS PRECLUDED BY SNOW COVER OR FROZEN GROUND

CONDITIONS STABILIZATION MEASURES MUST BE INITIATED AS SOON AS PRACTICABLE.

- B. WHERE CONSTRUCTION ACTIVITY ON A PORTION OF THE SITE IS TEMPORARILY CEASED, AND EARTH-DISTURBING ACTIVITIES WILL BE RESUMED WITHIN 14 DAYS, TEMPORARY STABILIZATION MEASURES DO NOT HAVE TO BE INITIATED ON THAT PORTION OF THE SITE.
- 3. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK, WITH NO TIME PERIOD BETWEEN INSPECTIONS EXCEEDING 9 DAYS, AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE. IT IS RECOMMENDED THAT BMPS BE ASSESSED BY THE CONTRACTOR WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 1.0 INCH OR GREATER, AS WELL AS DURING THE FIRST RAIN EVENT AFTER THE INITIATION OF CONSTRUCTION ACTIVITIES, AFTER THE INSTALLATION OF BMPS. IF PERIODIC INSPECTION OR OTHER INFORMATION INDICATES THAT A BMP HAS BEEN INAPPROPRIATELY OR INCORRECTLY INSTALLED, THE PERMITTEE MUST ADDRESS THE NECESSARY REPLACEMENT OR MODIFICATION REQUIRED TO CORRECT THE BMP WITHIN 48 HOURS OF IDENTIFICATION.
- 4. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES, AS MAY BE REQUIRED, TO CONTROL SOIL EROSION DURING UTILITY CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED, AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE UTILITY INSTALLATION. FILL, COVER, AND TEMPORARY SEEDING AT THE END OF EACH DAY ARE RECOMMENDED. IF WATER IS ENCOUNTERED WHILE TRENCHING, THE WATER SHOULD BE FILTERED TO REMOVE ANY SEDIMENTS BEFORE BEING PUMPED BACK INTO ANY WATERS OF THE STATE.
- 5. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ADDITIONAL CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION IN ORDER TO CONTROL EROSION AND/OR OFFSITE SEDIMENTATION. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETE AND THE SITE IS STABILIZED.
- 6. THE CONTRACTOR MUST TAKE NECESSARY ACTION TO MINIMIZE THE TRACKING OF MUD ONTO PAVED ROADWAY(S) FROM CONSTRUCTION AREAS AND THE GENERATION OF DUST. THE CONTRACTOR SHALL DAILY REMOVE MUD/SOIL FROM PAVEMENT, AS MAY BE REQUIRED.
- 7. TEMPORARY DIVERSION BERMS AND/OR DITCHES WILL BE PROVIDED AS NEEDED DURING CONSTRUCTION TO PROTECT WORK AREAS FROM UPSLOPE RUNOFF AND/OR TO DIVERT SEDIMENT-LADEN WATER TO APPROPRIATE TRAPS OR STABLE OUTLETS.
- 8. ALL WATERS OF THE STATE (WOS), INCLUDING WETLANDS, ARE TO BE FLAGGED OR OTHERWISE CLEARLY MARKED IN THE FIELD. A DOUBLE ROW OF SILT FENCE IS TO BE INSTALLED IN ALL AREAS WHERE A 50-FOOT BUFFER CAN'T BE MAINTAINED BETWEEN THE DISTURBED AREA AND ALL WOS. A 10-FOOT BUFFER SHOULD BE MAINTAINED BETWEEN THE LAST ROW OF SILT FENCE AND ALL WOS.
- LITTER, CONSTRUCTION DEBRIS, OILS, FUELS, AND BUILDING PRODUCTS WITH SIGNIFICANT POTENTIAL FOR IMPACT (SUCH AS STOCKPILES OF FRESHLY TREATED LUMBER) AND CONSTRUCTION CHEMICALS THAT COULD BE EXPOSED TO STORM WATER MUST BE PREVENTED FROM BECOMING A POLLUTANT SOURCE IN STORM WATER DISCHARGES.
- 10. A COPY OF THE OS-SWPPP, INSPECTIONS RECORDS, AND RAINFALL DATA MUST BE RETAINED AT THE CONSTRUCTION SITE OR A NEARBY LOCATION EASILY ACCESSIBLE DURING NORMAL BUSINESS HOURS, FROM THE DATE OF COMMENCEMENT OF CONSTRUCTION ACTIVITIES TO THE DATE THAT FINAL STABILIZATION IS REACHED.
- 11. INITIATE STABILIZATION MEASURES ON ANY EXPOSED STEEP SLOPE (3H:1V OR GREATER) WHERE LAND DISTURBING ACTIVITIES HAVE PERMANENTLY OR TEMPORARILY CEASED, AND WILL NOT RESUME FOR A PERIOD OF 7 CALENDAR DAYS.
- 12. MINIMIZE SOIL COMPACTION AND, UNLESS INFEASIBLE, PRESERVE TOPSOIL.
- 13. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM EQUIPMENT AND VEHICLE WASHING, WHEEL WASH WATER, AND OTHER WASH WATERS. WASH WATERS MUST BE TREATED IN A SEDIMENT BASIN OR ALTERNATIVE CONTROL THAT PROVIDES EQUIVALENT OR BETTER TREATMENT PRIOR TO DISCHARGE;
- 14. MINIMIZE THE DISCHARGE OF POLLUTANTS FROM DEWATERING OF TRENCHES AND EXCAVATED AREAS. THESE DISCHARGES ARE TO BE ROUTED THROUGH APPROPRIATE BMPS (SEDIMENT BASIN, FILTER BAG, ETC.).
- 15. THE FOLLOWING DISCHARGES FROM SITES ARE PROHIBITED:
- A. WASTEWATER FROM WASHOUT OF CONCRETE, UNLESS MANAGED BY AN APPROPRIATE CONTROL;
- B. WASTEWATER FROM WASHOUT AND CLEANOUT OF STUCCO, PAINT, FORM RELEASE OILS, CURING COMPOUNDS AND OTHER CONSTRUCTION MATERIALS;
- C. FUELS, OILS, OR OTHER POLLUTANTS USED IN VEHICLE AND EQUIPMENT OPERATION AND MAINTENANCE; AND
- D. SOAPS OR SOLVENTS USED IN VEHICLE AND EQUIPMENT WASHING.
- 17. AFTER CONSTRUCTION ACTIVITIES BEGIN, INSPECTIONS MUST BE CONDUCTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK, WITH NO TIME PERIOD BETWEEN INSPECTIONS EXCEEDING 9 DAYS AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE.
- 18. IF EXISTING BMPS NEED TO BE MODIFIED OR IF ADDITIONAL BMPS ARE NECESSARY TO COMPLY WITH THE REQUIREMENTS OF THIS PERMIT AND/OR SC'S WATER QUALITY STANDARDS, IMPLEMENTATION MUST BE COMPLETED BEFORE THE NEXT STORM EVENT WHENEVER PRACTICABLE. IF IMPLEMENTATION BEFORE THE NEXT STORM EVENT IS IMPRACTICABLE, THE SITUATION MUST BE DOCUMENTED IN THE SWPPP AND ALTERNATIVE BMPS MUST BE IMPLEMENTED AS SOON AS REASONABLY POSSIBLE.
- 19. A PRE-CONSTRUCTION CONFERENCE MUST BE HELD FOR EACH CONSTRUCTION SITE WITH AN APPROVED ON-SITE SWPPP PRIOR TO THE IMPLEMENTATION OF CONSTRUCTION ACTIVITIES. FOR NON-LINEAR PROJECTS THAT DISTURB 10 ACRES OR MORE THIS CONFERENCE MUST BE HELD ON-SITE UNLESS THE DEPARTMENT HAS APPROVED OTHERWISE.

14 DAY STABILIZATION CLAUSE

ALL DISTURBED AREAS WHICH ARE TO BE LEFT IDLE FOR A PERIOD OF 14 DAYS OR LONGER ARE TO RECEIVE TEMPORARY VEGETATION OR MULCH.

EROSION CONTROL MAINTENANCE SCHEDULE

ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK, WITH NO TIME PERIOD BETWEEN INSPECTIONS EXCEEDING 9 DAYS, AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE. IT IS RECOMMENDED THAT BMPS BE ASSESSED BY THE CONTRACTOR WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 1.0 INCH OR GREATER, AS WELL AS DURING THE FIRST RAIN EVENT AFTER THE INITIATION OF CONSTRUCTION ACTIVITIES, AFTER THE INSTALLATION OF BMPS. CONTRACTOR TO DOCUMENT WITH SCDHEC APPROVED INSPECTION REPORTS AND LOGGED IN THE PROJECT

OS-SWPPP.

GENERAL NOTES:

- 1. REFERENCE IS MADE TO THE FOLLOWING:
- A. BOUNDARY AND TOPOGRAPHIC SURVEY PREPARED FOR RICHLAND COUNTY SCHOOL DISTRICT TWO BY THE JOHN R. MCADAMS COMPANY, INC., DATED JULY 7, 2021.
- 2. ALL ELEVATIONS SHOWN REFER TO NAVD 88 DATUM.
- 3. HORIZONTAL COORDINATES REFER TO NAD 83 (2011 ADJUSTMENT) SOUTH CAROLINA STATE PLANE COORDINATE SYSTEM.
- 4. THE LOCATIONS OF EXISTING UNDERGROUND UTILITIES ARE SHOWN IN AN APPROXIMATE WAY ONLY. VERIFY ALL FIELD CONDITIONS AND THE EXACT LOCATIONS OF ALL UNDERGROUND UTILITIES PRIOR TO BEGINNING DEMOLITION AND CONSTRUCTION. IF CONDITIONS ARE DIFFERENT FROM THAT SHOWN ON THE PLANS, STOP WORK AND NOTIFY THE ENGINEER.
- 5. ALL WORK FOR THE PROJECT SHALL CONFORM TO THE PROJECT SPECIFICATIONS FOUND IN THE PROJECT MANUAL (CONTRACT DOCUMENTS AND SPECIFICATIONS).
- 6. CONTRACTOR IS RESPONSIBLE FOR THE LAYOUT OF THE PROPOSED SITE AND LIMITS OF WORK.
- 7. ANY UTILITIES OR FACILITIES DAMAGED DURING THE PROJECT BY THE CONTRACTOR'S PERSONNEL OR EQUIPMENT SHALL BE PROMPTLY REPAIRED AT THE CONTRACTOR'S EXPENSE. HAND DIGGING TO PROTECT UTILITIES FROM DAMAGE SHOULD BE ANTICIPATED.
- 8. THE CONTRACTOR IS RESPONSIBLE FOR CONDUCTING WORK IN ACCORDANCE WITH THE LATEST REQUIREMENTS AND REGULATIONS OF THE OCCUPATIONAL SAFETY AND HEALTH ADMINISTRATION (OSHA).
- 9. ALL DEMOLITION DEBRIS, INCLUDING CLEARING AND GRUBBING SHALL BE DISPOSED OF OFF-SITE IN ACCORDANCE WITH ALL LOCAL, STATE AND
- 10. PROMPTLY INFORM THE ENGINEER OF ANY ERROR OR DISCREPANCIES DISCOVERED IN THE DRAWINGS OR SPECIFICATIONS OR CONFLICTS BETWEEN THE DRAWING AND SPECIFICATIONS IN ORDER FOR CORRECTIONS TO BE MADE.
- 11. ALL WORK AND MATERIALS MUST CONFORM WITH GREENVILLE COUNTY AND SOUTH CAROLINA DEPARTMENT OF HEALTH AND ENVIRONMENTAL CONTROL (SCDHEC) REGULATIONS AND SPECIFICATIONS, LATEST REVISIONS AT THE BEGINNING OF CONSTRUCTION.
- 12. KEEP ALL ADJACENT AREAS TO THE LIMITS OF WORK CLEAN AND FREE OF DEBRIS/MATERIALS/EQUIPMENT AT ALL TIMES.
- 13. CONTRACTOR RESPONSIBLE FOR PREPARING AND OBTAINING APPROVAL OF ALL TRAFFIC CONTROL PLANS AND LAYOUT AS REQUIRED FOR THE DURATION OF THE PROJECT.
- 14. ANY POSSIBLE STOCKPILES, OFFSITE MATERIAL, WASTE, BORROW, OR CONSTRUCTION EQUIPMENT STORAGE / LAYDOWN AREAS SHALL BE LOCATED WITHIN THE LIMITS OF DISTURBANCE.
- 15. THE CONCRETE WASHOUT SHALL BE LOCATED WITHIN THE LIMITS OF DISTURBANCE.

GRADING AND EROSION CONTROL NOTES:

FEDERAL REGULATIONS AND SPECIFICATIONS, LATEST REVISION.

- 1. EXISTING UNDERGROUND UTILITIES SHALL BE FIELD VERIFIED PRIOR TO INSTALLATION OF ANY NEW PIPE LINES OR GRADING OPERATIONS.
- 2. WHEN GRADING BETWEEN CONTOURS AND BETWEEN POINTS OF SPOT ELEVATIONS, GRADE ON A UNIFORM SLOPE. PROPOSED GRADES SHOWN ARE FINAL SURFACE ELEVATIONS.
- 3. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE ON ALL FINISHED GRADE SURFACES ONCE BUILDING SLABS AND FOUNDATIONS ARE REMOVED.
- 4. EACH SECTION OF STORM DRAINAGE PIPE SHALL BE LAID TO SPECIFIED GRADE AND LAID UPGRADE.

5. ALL VEGETATION TOPSOIL SHALL BE STRIPPED AND STOCKPILED PRIOR TO PLACING FILL, PROTECT STOCKPILE FROM EROSION.

- 6. CONTRACTOR SHALL, FOR ALL GRASSED AREAS, BE RESPONSIBLE FOR REPLACING ERODED SOIL AND GRASS SEED UNTIL AN APPROVED STAND OF GRASS IS ESTABLISHED.
- 7. PROPOSED FILL SOILS SHALL BE SUITABLE MATERIAL AND FREE OF ORGANIC MATERIAL, RUBBLE, DEBRIS, AND HIGHLY PLASTIC CLAYS OR SILTS.
- 8. REMOVE ALL ORGANIC AND UNSUITABLE MATERIAL (MUCK AND/OR NON-COMPACTABLE MATERIAL) FROM AREAS TO BE FILLED.
- 9. CONTRACTOR SHALL, BEFORE BEGINNING GRADING WORK ON SITE, STAKE SILT FENCE AND INSTALL ALL PERIMETER EROSION CONTROLS AS SHOWN IN THESE PLANS.
- 10. CONTRACTOR SHALL BE AWARE OF EXISTING UTILITY LINES DURING PIPE LINE INSTALLATION. CONTRACTOR SHALL NOTIFY UTILITY COMPANIES SUCH AS THE LOCAL ELECTRIC COMPANY, AT&T, ETC. FOR LOCATION OF OTHER UTILITIES NOT SHOWN ON PLAN. CALL PALMETTO UTILITIES PROTECTION SERVICES (SC811) FOR UNDERGROUND UTILITY LINES LOCATION. THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES PRIOR TO CONSTRUCTION.
- 11. ALL NEWLY CONSTRUCTED SLOPES WHICH ARE STEEPER THAN OR EQUAL TO 2.5 TO 1 MUST BE STABILIZED BY INSTALLATION OF EROSION CONTROL MATTING. OTHER AREAS SUCH AS CHANNEL BOTTOMS, CHANNEL SIDESLOPES, AND SLOPES NEAR SENSITIVE WETLAND AREAS MAY ALSO REQUIRE EROSION CONTROL MATTING WHERE SHOWN ON PLANS. USE NORTH AMERICAN GREEN (NAG) ROLLMAX SC150 OR APPROVED EQUAL WHERE CHANNEL PROTECTION/EROSION CONTROL MATTING IS SPECIFIED ON THE PLANS UNLESS OTHER SPECIFIC MATERIAL IS CALLED OUT ON PLAN SHEET. EQUAL PRODUCTS MUST BE APPROVED BY THE ENGINEER PRIOR TO INSTALLATION.
- 12. PROVIDE SILT FENCE AND/OR OTHER CONTROL DEVICES AS MAY BE REQUIRED TO CONTROL SOIL EROSION DURING CONSTRUCTION. ALL DISTURBED AREAS SHALL BE CLEANED, GRADED AND STABILIZED WITH GRASSING IMMEDIATELY AFTER THE SITE IMPROVEMENTS ARE COMPLETED.
- 13. ALL AREAS OUTSIDE OF THE LIMITS OF WORK WHICH ARE DISTURBED BY CONSTRUCTION ACTIVITIES SHALL BE SEEDED AT NO ADDITIONAL EXPENSE TO THE OWNER.
- 14. INSTALL PERMANENT VEGETATIVE COVER AND THE LONG-TERM EROSION PROTECTION MEASURES OR STRUCTURES AS SOON AS PRACTICAL IN THE DEVELOPMENT PROCESS.
- 15. ALL DISTURBED AREAS NOT PAVED SHALL BE GRASSED OR LANDSCAPED. USE TEMPORARY PLANT COVER, MULCHING, AND/OR STRUCTURES TO CONTROL RUNOFF AND PROTECT AREA SUBJECT TO EROSION DURING CONSTRUCTION.
- 16. ALL SEDIMENT AND EROSION CONTROL DEVICES SHALL BE INSPECTED AT A MINIMUM OF AT LEAST ONCE EVERY CALENDAR WEEK, WITH NO TIME PERIOD BETWEEN INSPECTIONS EXCEEDING 9 DAYS, AND MUST BE CONDUCTED UNTIL FINAL STABILIZATION IS REACHED ON ALL AREAS OF THE CONSTRUCTION SITE. IT IS RECOMMENDED THAT BMPS BE ASSESSED BY THE CONTRACTOR WITHIN 24 HOURS OF THE END OF A STORM EVENT OF 1.0 INCH OR GREATER, AS WELL AS DURING THE FIRST RAIN EVENT AFTER THE INITIATION OF CONSTRUCTION ACTIVITIES, AFTER THE INSTALLATION OF BMPS. MAINTENANCE OF SEDIMENT TRAPPING DEVICES SHALL BE PERFORMED AS NECESSARY PER THESE INSPECTIONS. DAMAGED OR INEFFECTIVE DEVICES SHALL BE REPAIRED OR REPLACED, AS NECESSARY.
- 17. ADDITIONAL EROSION CONTROL DEVICES MAY BE REQUIRED DURING CONSTRUCTION TO CONTROL EROSION AND/OR OFF SITE SEDIMENTATION. CONTRACTOR IS RESPONSIBLE FOR MAINTAINING THE STABILITY OF ALL GRADED AND/OR CLEARED AREAS UNTIL PERMANENT GROUND COVER IS ESTABLISHED. ANY AREAS DAMAGED BY EROSION SHALL BE REPAIRED TO ITS ORIGINAL CONDITION AND PROTECTED FROM FURTHER EROSION AT NO ADDITIONAL COST TO THE OWNER.
- 18. ALL EROSION CONTROL DEVICES SHALL BE PROPERLY MAINTAINED DURING ALL PHASES OF CONSTRUCTION UNTIL THE COMPLETION OF ALL CONSTRUCTION ACTIVITIES AND ALL DISTURBED AREAS HAVE BEEN STABILIZED. ALL TEMPORARY CONTROL DEVICES SHALL BE REMOVED ONCE CONSTRUCTION IS COMPLETED AND THE SITE STABILIZED.
- 19. ALL EROSION CONTROL METHODS SHALL BE IN ACCORDANCE WITH "SCDHEC STORM WATER MANAGEMENT & SEDIMENT CONTROL BMP HANDBOOK FOR LAND DISTURBANCE ACTIVITY".
- 20. ALL DISTURBED AREAS, INCLUDING THE CONTRACTORS STAGING AREA, HAUL ROUTES, GRADING LIMITS, ETC., SHALL BE RESTORED TO A SMOOTH LINE AND GRADE WITH POSITIVE DRAINAGE. THE CONTRACTOR SHALL PERMANENTLY SEED ALL DISTURBED AREAS.
- 21. CONTRACTORS ARE REQUIRED TO HAVE RAIN GAUGES AT THE CONSTRUCTION SITE AND THE RAIN TOTALS DOCUMENTED FOR REVIEW BY SCDHEC.
- 22. THE INSTALLATIONS OF UTILITIES (CABLE, ELECTRICAL, NATURAL GAS, WATER, SEWER, ETC.) ARE TO BE WITHIN THE PERMITTED LIMITS OF
- DISTURBANCE AND THAT INSTALLATION OUTSIDE OF THESE AREAS WILL REQUIRE A MODIFICATION TO THE PERMIT.

 23. THE STABILIZATION OF CONVEYANCE CHANNELS ARE TO BE COMPLETED WITHIN 7 DAYS OF CHANNEL CONSTRUCTION (IF THERE ARE CHANNELS).

NOTICE TO CONTRACTOR

1. PRIOR TO CONSTRUCTION, DIGGING, OR EXCAVATION THE CONTRACTOR IS RESPONSIBLE FOR LOCATING ALL UNDERGROUND UTILITIES (PUBLIC OR PRIVATE) THAT MAY EXIST AND CROSS THROUGH THE AREA(S) OF CONSTRUCTION, WHETHER INDICATED ON THE PLANS OR NOT. CALL "811" A MINIMUM OF 72 HOURS PRIOR TO DIGGING OR EXCAVATING. REPAIRS TO ANY UTILITY DAMAGED RESULTING FROM CONSTRUCTION ACTIVITIES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.



CRAİG GAULDEN DAVIS

> Planning Interiors 19 Washington Park

> > Greenville, SC 29601

Phone 864.242.0761

Fax 864.501.9945 E-mail cgd@cgdarch.com

Architecture

COPYRIGHT © 2022 CRAIG GAULDEN & DAVIS, INC.

ALL RIGHTS RESERVED

THIS COPYRIGHTED DOCUMENT AND ALL INFORMATION CONTAINED HEREIN IS AN INSTRUMENT OF SERVICE AND SHALL NOT BE REPRODUCED, ALTERED, OR REUSED IN PART OR IN WHOLE WITHOUT PRIOR WRITTEN PERMISSION FROM THE ARCHITECT. THIS DRAWING IS THE EXCLUSIVE PROPERTY OF THE ARCHITECT AND MUST BE RETURNED UPON REQUEST.

CONSULTANT



WKD PROJECT NO.: 20220226.00.CA

GREENVILLE COUNTY SCHOOLS

BUILDING DEMOLITION PACKAGE

301 E. CAMPERDOWN WAY, GREENVILLE SC, 29601

DATE MARK DESCRIPTION

ISSUE: CONSTRUCTION DOCUMENTS


DATE: July 29,2022


PROJECT NO: 22030


DRAWN BY: BAD


GENERAL NOTES

C100










6 5 2



July 29,2022

22030

BAD

CWC