

2023 Summer Painting

Scope of Work

Maintenance Painting

1. General Information

A. Definitions

- 1. The Owner is the School District of Greenville County
- 2. The Project Manager shall represent the Owner
- 3. The Work is Maintenance Painting of:

NAME OF SCHOOLS HERE	Total Sq. Ft.	Approx. to be Painted
Berea Bus Center	1440	
Blue Ridge MS	135110	
Bryson ES	107491	
Cherrydale ES	83210	
Golden Strip CC	74906	
Grove ES	97312	
Mauldin HS	138962	
Monarch ES	107396	
Monaview ES	92519	
Oakview ES	114993	
Paris ES	72200	
Robert Cashion ES	101378	
Sterling / Townes K-8	132505	
Tigerville ES	65577	

These Numbers DO NOT include any athletic facility square footages.

- 4. The Contractor is the successful bidder chosen to do the Work.

5. The Work Schedule is the approved schedule between The Owner and the Contractor to complete the Work.
6. School Hours are 7:00 AM - 4:30 PM Monday through Friday.
7. School Summer Hours are 7:30 AM – 5:30 PM Monday through Thursday, - closed on Fridays from June 6, till August 6, 2022.
8. School Holidays are those days when administrative staff is working but no students are at the school.
9. School Closed days are those days no one is working at the school.

B. Work Schedule

The Successful Contractor shall provide to the Owner a schedule for the work. The Notice to Proceed shall reflect the Date of Commencement and the Date of Completion based upon this Work Schedule agreement. All work shall be substantially completed (as evidence by the date on the CERTIFICATE OF SUBSTANTIAL COMPLETION) as follows:

1. The Work shall be substantially completed during school summer hours on the interior and high use exterior doors of the buildings for all the facilities by: July 29, 2023.

Exterior areas are to be completed on or before September 30, 2023.
2. The Contractor may work non-school hours with approval from the Owner. Prior approval by the Owner is required no less than twenty-four hours in advance to insure a means of entering and securing the building is in place.
3. The Contractor shall submit in writing to the Project Manager of any change to the Work Schedule. Only approved changes in the Work Schedule are acceptable under this agreement.

C. Changes in the Work

1. Change Order will accommodate any changes in the Work after execution of the Contract without invalidating the contract.
2. A Change Order shall be based on an agreement between Owner and Contractor and must be submitted in writing for Owner's approval. Approval of the Change Order must be received before the execution of the Work.
3. Only approved Change Orders will be part of Work

D. Contractor Liability

1. Contractor shall be responsible for any damage to or loss of property that resulted from the Contractor's presence on the property. Any damages or property loss shall be repaired or replaced by the Contractor to the Owner's satisfaction at no cost to the Owner.
2. The Contractor shall provide certificate of liability insurance as required in the contract document for general liability and vehicle liability.

E. Contractor Licensing

Contractor shall be licensed in full accordance with the laws of the State of South Carolina as amended to perform the work as defined in this contract.

II. SCOPE OF WORK

A. Contractor shall provide all materials, equipment, tools, consumables, labor, cleanup, waste and debris disposal, and supervision necessary to complete within the defined schedule and specifications the maintenance painting of the facilities listed. Maintenance painting shall consist of the following:

1. Paint shall be applied to all previously field painted surfaces on the interior and exterior of the buildings as defined in the "Attachment A".
2. Properly prepare surfaces to ensure a strong bond over existing painted surfaces. Preparation is the key to a strong bond and every effort is to be made to ensure the new paints adhere to all existing surfaces on the interior and exterior of the facilities.

The preparation of existing surfaces is the most important step in the process and every effort shall be made by the Contractor to ensure the proper adhesion of the new paint coatings. Those surfaces that are handled by daily student and staff traffic are especially difficult due to hand oils left on these surfaces. Contractor shall be responsible to redo any surfaces where adhesion fails by removing failed paint film and properly preparing surface and applying new paint to the Owner's satisfaction.

3. Finish paint materials:

Exterior: All exterior surfaces shall be painted with High Performance Acrylic finishes that have high color retention and high durability. Due to the required thirty-day cure of the acrylic products the painting of handrails, columns, and high use doors shall consist of products that have the fastest cure time for the application.

- a. Exterior High Performance Enamel: Factory-Formulated full gloss/semi-gloss enamel for exterior application with high color retention.
 - Sherwin-Williams: Sher-Kem™ High Gloss Metal Finishing Enamel: Applied at a dry film thickness of not less than 1 to 2.0 mils per coat. Best applied by spray application. This product is given as an alternative to acrylic in areas of high traffic due to faster cure time.
 - Sherwin-Williams: Steel Master 9500 30% Silicon Alkyd Enamel B56-300 series, applied at a dry film thickness of not less than 2-3 mils per coat. This product is given as an alternative for the acrylic in areas of high traffic due to faster cure time. This product is formulated for easy brush application.
 - Sherwin-Williams: Sher-Cryl™ High Performance Acrylic: B66-300 series Gloss or B66-350 series Semi-Gloss. Applied at a dry film thickness of not less than 2.5-4 mils per coat. To be used on exterior areas assuring the thirty day cure time.
 - Owner approved equal by a listed approved Manufacturer.

Interior: All walls on the interior of buildings shall be painted with Pre-Catalyzed one component water-born epoxy in semi-gloss or eggshell sheen.

a. Interior Semi-Gloss/eggshell water-born precatalyzed one component Epoxy Coating

- Duron: Dura-Clad Industrial Coatings: Acrylic Epoxy- 901-0002: Applied at a dry film thickness of not less than 1.5 mils per coat.
- Sherwin-Williams: Water-Born Epoxy Precatalyzed one component K46W51 Series. Applied at a dry film thickness of not less than 1.5 mils per coat.
- Owner approved equal by an approved Manufacturer.

b. NOTE: Important note on tinting: Provide tints for Pre-catalyzed Water-based Epoxy finishes that ensure the fastest curing and early adhesion especially when using deep accent colors requiring high levels of tint.

REFERENCE: Sherwin-Williams: Pre-Catalyzed Water based Epoxy: Tint with Enviro-toner Colorants or equal for Owner approved equal products by listed approved Manufacturers.

Painted ceilings shall be a flat ceiling white unless noted as exception in scope of work for each location listed below.

4. Application of finish paint materials:

Exterior: Two coats are to be applied to all exterior surfaces including the inside and outside of exterior doors and jambs. Exterior surfaces such as but not limited to hollow metal doors, jambs, windows, painted masonry lintels, ceilings, support columns, bollards, signs, playground goal posts, and exterior lighting (including wall units and poles and light fixtures) shall be painted. Ferrous metal surfaces shall be painted with High Performance finishes as listed above.

Interior: One coat to cover on walls, painted ceilings, metal doors, and hollow metal frames when matching existing color and sheen or two coats to cover when changing paint Color. Exception: Interior Toilet Rooms and kitchen dishwashing rooms shall have two coats applied.

5. Interior Wood Doors: Clear top coat applied after proper preparation.

6. Work Coordination: Review areas to be painted and coordinate with the Owner a schedule of areas to be painted so that the daily operation of the school and scheduled cleaning would be minimally impacted. Informing the Owner of relocation and removal of equipment, computers, etc., that would need to be disconnected and moved for painting to occur.

7. Work Area Preparation and Clean-up: Custodial Staff shall prepare the work area by pulling the freestanding bookshelves and other furniture, desks, chairs, movable storage cabinets away from the surfaces to be painted.

Contractor shall properly cover during the surface preparation and painting process. Custodial Staff shall remove blinds to ensure proper painting of windows and reinstall when painting of window is complete. Contractor shall provide covering by drop cloth or masking of all surfaces that are not to be painted during the preparation process. Remove hardware and hardware accessories, fire rating plates, and similar items that are not to be painted. If removal is impractical or impossible, surface-applied protection such drop cloth or masking shall be in place before surface preparation and painting begins. Cover and mask all surfaces that are not to be painted, floors, trim, smoke detectors, burglar alarm devices, return air ducts, furniture, equipment, built-in bookcases, cabinets and surfaces that are not to be painted. After completing painting operations in each space or area, reinstall items removed by placing back in original position, uncover and unmask and touch up. Covering shall ensure that paint, paint chips, dust, solvent drips, and debris from the process are prevented from getting onto those surfaces not to be painted and contained as not to migrate into adjoining areas. Schedule cleaning and painting so dust and other contaminants from the cleaning process will not fall on wet, newly painted surfaces. The work area shall be maintained clean on a daily basis. It is recommended that the painting of the covered area be completed before removing covering.

The Contractor shall ensure that any and all adjacent areas and surfaces are covered and vehicles are relocated during exterior spray applications of paint. Due to wind-born overspray it is strongly suggested that exterior spraying of paint be minimized and Contractor shall be responsible for control of the overspray and to resolve any resulting damage to cars and surfaces holding the Owner harmless in the action.

8. All murals and wall painted signage shall not be painted over unless specifically called out and identified by the Owner.

9. Protect all door labels on fire doors.

B. Scope of Work by Location as listed below includes Section A above and additions and omissions or specific site paint details.

Some locations will be listed as "Core Spaces", some will be listed at "All Spaces", others will be listed as "Partial Spaces".

New Quality Control Procedures

All paint projects shall adhere to the following quality procedures and properly document with material supplier for final summary report.

Contractor shall coordinate evaluations of all walls, door, door frames and store front frames conditions with the assistance of material supplier per the followings:

Step 1 Have walls, doors and frames evaluated using standard pull test to identify any problems. Any unusual conditions shall be brought to the attention of the School District Project Manager.

Step 2 Clean all walls giving special attention to the area 48" above finished floor. Refer to section E on page 64 for detailed preparation procedures. Use Great Lakes No Rinse Cleaner or approved equal.

Step 3 Periodically perform wet film check for assurance to specification.

Step 4 Perform post paint evaluation for adherence to specifications.

Berea Bus Center – Approx sq. ft. 1440

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Paint all handrails, interior and exterior. Prepare surfaces for proper adhesion prior to painting. (extra attention)

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws or hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

This site consist of two portable type buildings, one for Staff and one for Drivers.

Paint all paintable metal doors and frames, including MDF Doors and frames, both sides.

Staff Building – Protect bus mural in entrance

Paint all walls throughout

Driver's Building – Paint all walls and ceilings throughout.

Blue Ridge Middle School – Approximately 135,110 sq. ft.

Color selections will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Prepare surfaces for proper adhesion prior to painting.

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws of hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

Front Hallway – Paint all exterior and interior walls

Paint all ductwork, color change.

Paint all interior soffits, color change.

Cafeteria/Kitchen Areas

Paint all walls in cafeteria area, soffit area color change

Service line, paint all walls, accent back serving line wall (both sides). Cover murals. Color change on soffit area.

Food prep area and office, paint all walls, add accent wall in office. Color change on soffit area in serving line.

Locker room and restrooms, paint all walls.

Gym

Paint all gym walls to ceiling, color change, protect tiger mural. Paint sound panels.

Paint ceiling steel and pipe and conduit.

Paint main bb goal steel supports (do not paint side goals steel).

Locker Rooms (2) – Paint all walls, paint over murals. Paint locker room benches, color change.

Paint restroom walls.

Paint gym offices walls, color change. Add accent wall opposite door.

Gym Hallway – Paint walls, add stripe 1 block at top both sides. Paint accent wall at entry wall

Weigh Room – Paint walls, sound panels, doors and soffits, cover lettering. Add 2 block accent include soffit.

Custodian Hallway – Paint all walls

Custodian Office and staging area – Paint all walls

Receiving Area – Do Not Paint

Do not paint laundry area

Hallway/Lobby outside gym – Paint walls, paint accent stripe, top two blocks

Restrooms – paint all walls, add accent on entry wall outside corner to inside corner.

Main Entrance/outside auditorium

Auditorium – Paint all walls to ceiling, cover teal color and conduit.

Stage Front – paint black

Back stage wall, paint black

Side stage doors, paint black

Handrails, paint to match.

Health Room – Paint all walls

Paint shower area and restrooms

Paint Cot Area walls, accent back walls

PTSA Room – Paint all wall in office and store area

Media Center Area

ISS area – Paint all walls

Offices (2) – Paint all walls

Room 412 – Paint all walls

Group Restroom – Paint all walls

Hallway Connector – Paint all walls, color change drywall at main hall connector.

Related Arts Hall – Paint all walls, Accent end walls and water cooler areas (inside corner to corner)

Paint all classroom walls, accent exterior walls, opposite doors.

Paint all sound panels in area include classrooms.

Room 515, no accents

Rooms 409 and 410 – Paint all walls, accent right walls.

Room 50 – Paint all walls

6th, 7th and 8th grade Halls

Paint all hall walls, accent end walls and water cooler areas (inside corner to corner)

Paint all classroom walls, accent wall opposite doors

Administration Area

Paint all hall walls, paint all offices, accent wall opposite doors

Paint all walls in workrooms and restrooms.

Lobby – Paint all walls, protect mural

Exterior

E.I.F.S. on exterior of gym and front of school.

Storage Building exterior, exterior door and frame in back of school.

Base Ball Field Concession Building & Press box, interior and exterior. Pattern to be 3 color stripes on building, black, red stripe to be two blocks high and white stripe extended lower by one block. Paint interior of building neutral.

Wood Structure, match pattern of block structure. Do not paint interior of wood structure.

Bryson Elementary – Approximately 107,491 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Paint all handrails, interior and exterior. Prepare surfaces for proper adhesion prior to painting. (extra attention)

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws or hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

Cafeteria – Protect all murals on all columns.

Clearstory – Paint all walls, color change

Stage Area – Paint all steel. Paint all drywall, white.

Eating Area Bulkhead – Paint all vertical surface, accent color. Paint horizontal surface and ceiling white.

Food Prep – Paint all walls

Outside Can Wash Area – Paint all lintels, doors

Gym

Ceiling Steel and deck – Paint all surfaces

Office Restroom and Student Restrooms – Paint all walls

Sloped inside room Area – Paint black

High Wall next to sloped area – Pant High Wall Blue

Side Gym Walls – Lower existing grey, color change. Paint strip as existing. Paint high wall, white duck.

Media Center

Reading Area (Tables) – Paint ceiling drywall, accent all sides. Paint ceiling white.

Conference Room – Pant all walls, accent walls opposite doors.

Office – Paint all walls, accent

Main Media Walls – Paint all walls.

Media Production – Protect mural, paint green screen on existing, paint others neutral.

Group Toilets Near Cafeteria – entry wall, corner around to inside corner. Paint all other walls. Paint stripe at top around each restroom.

Men RR sink area – 45 degree scuff and paint supports.

Guidance Area

Paint all offices, accent wall opposite door.

Skip conference room

Kindergarten Hall

Kindergarten and 1st grade Classrooms – Paint all walls in classroom, restrooms and connecting offices.

Room 10 – Paint all walls, accent window wall.

Hallways – Paint all walls. Add stripe at top 8” both sides.

Water Cooler Area – Paint accent inside corner to classroom doors area. Paint accent on end wall.

Main Hall – Paint walls, accent stripe at top both sides. Cover mural, P.A.W.S.ITIVE. Purple color, color change.

Handrails – Paint all hall handrail, black.

Art Room – Paint same as classroom

Island Classrooms – Paint all hall walls.

Conference Rooms (2) – Paint all wall (3rd/4th grades).

Lintels – Paint already painted lintels only.

Classrooms – Paint all wall in all classrooms, accent window walls, corner to corner.

Single Toilets – throughout school

Paint all walls, neutral.

Group Toilets – Paint all walls, accent entry walls around to inside corner.

Front Entry

Ceiling – Paint white

Walls – Paint all walls, color change

Drywall – Paint white.

Reception Area – Paint all walls, accent back wall.

Main Office Area – Paint all walls, accent back wall

Restrooms – Paint all walls, neutral

Nurse Area – Protect Mural, Paint all other walls, neutral.

Conference Room – Paint all walls, cover logo

Teacher’s Lounge – Paint all walls, accent wall wall opposite door.

Principal Office – Paint all walls, accent window wall.

All Offices – Paint all walls in all office, accent wall opposite door.

EXTERIOR:

Back Dock: Paint Lintels and doors.

Bollards at cafeteria loading dock – Paint safety yellow.

Bus Drive Canopy – Paint rails, bus canopy underdeck and steel

Front Entrance – Paint ceiling steel and texture material.

Cherrydale Elementary – Approximately 123,376 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Prepare surfaces for proper adhesion prior to painting.

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws or hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

Gym

Paint front of stage black

Paint all stage walls

Paint all handrails

Paint curved brick walls on either side of stage.

Paint all gym walls, color change for 2 stripes

Prep and paint all ductwork

Office and restrooms (office and student), paint all walls.

Office at top of ramp, paint all walls

Music Room - Paint all walls neutral and handrails to match

Science Room - Paint all walls, current accent to neutral, Teacher (Promethean) wall to new accent wall.

Art Room - Paint all walls, current accent to neutral, Teacher wall to new accent wall.

Room 716 – Paint all walls neutral, paint accent on right wall

Room 719 – Paint all walls neutral.

Room 718 – Paint all walls, accent teacher wall.

Stairways (3) – Paint risers black and stringers black. Paint handrails to match existing color

Hall walls leading to stair and corridors – Accent wall with water fountains (inside corners)

Accent drywall at ceiling, all other areas neutral

Office Entrance Lobby – Paint accent curved soffit, all other surfaces neutral.

Receptionist Area – Paint accent on back wall, paint all other walls neutral.

Main Front Entrance – Paint ceiling deck and steel. Paint all drywall, color change, Paint all block neutral, sprinkler match walls.

Media Center – Protect Murals except where noted

Entry Wall (curved), paint accent to ceiling.

Paint ceiling deck and steel

Paint existing accent wall, cover stars

Other wall neutral, cover stars

Back wall, extend accent

All other walls, neutral

Media Classroom – Accent wall, color change, all others neutral

Office – Paint all walls

Conference Room – Paint all walls, accent back walls

Cafeteria

Eating Area – Accent hallway entrance wall, paint all other walls neutral

Serving Line – Accent wall between serving and food prep area. Paint all other walls neutral

Office – Paint all walls

Locker room, hall and restrooms – paint all walls

Single Restrooms throughout school – Paint all walls

Classrooms throughout school, upstairs and downstairs

Paint all walls, accent teaching wall (with promethean boards)

Single Offices throughout school – Paint all walls

Group Restrooms and restroom entrance

Paint ceilings

Countertops – Paint countertops, accent, not supports

Left wall boys, Right wall girls

Upstairs

Group Restrooms and restroom entrance

Paint ceiling white, all walls, accent left wall boys, right wall girls

Health Room Area

Guidance Area

Administration Area

Golden Strip Career Center – 74,906 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Prepare surfaces for proper adhesion prior to painting.

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws of hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

Auditorium – Proper prep and repair all walls prior to painting. Paint all walls, color change

Storage Door – Prep and refinish storage room door

Classroom off Auditorium – Paint all walls

Food Prep Area – Paint all walls

Office Walls – Paint all walls, add accent one wall

Restroom/Locker Room – Paint all walls

Back Entry Ceiling – Repair and paint ceiling

Laundry Room – Paint all walls

Hallways – Paint all walls, neutral, paint 2 block max strip at top of wall

Restroom – paint all ceiling and walls

Cross Hallways – Paint all walls

Restrooms – Paint all walls and sink areas

Classrooms – All classrooms/Labs, Rooms with attic spaces are considered Laboratory Rooms. These spaces get all walls, attic walls, ladders and rails to be painted.

Room 200 – Paint all walls and office walls.

Paint all doors and door frames, black

Room 231 – Paint all walls, frames,

Paint all office walls, rooms 232 and 237

Room 207 – Paint all walls and ceiling

Paint office walls

Paint outside doors only, black

Room 214 – Paint all walls

Room 216 - Paint all walls and ceilings

Paint office walls

Attic and Rails – Paint walls and rails and ladder frames

Room 223 and 222 Paint all walls

Paint office walls

Room 226 Paint all walls and office walls, add accent wall

Room 351 Fire – Paint all walls and ceiling, office walls and restroom walls

Room 337 Machine Shop - Paint all walls and ceiling and office walls

Room 300 Mechatronics – Paint walls in office

Room 312 - Paint all walls, cover mural, paint walls including attic space. Paint rails and ladder steel.

Room 323 (Lab) - Paint all walls in classroom, attic area and metal rails and ladder.

Room 326 (Lab) – Paint all walls in classroom, attic area and metal rails and ladder.

Room 325 (Lab) – Paint all walls per lab. In paint booth area, walls outside paint booth.

Teacher Workroom/ Lounge Two Rooms – Paint all walls.

Room 130 (Lab) Paint all walls, above and below counters

Paint walls in storage room, office, locker room and restroom

Room 132 – Paint all walls in office, lab walls, locker room, restroom and kitchen area

Room 235 – Paint all walls

Administration Area - Paint all walls neutral throughout include entrance area and all offices.

Reception Area – Paint top cabinetry color change, paint lower cabinets dark blue

Grove Elementary – Approximately 97,312 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Paint all handrails, interior and exterior. Prepare surfaces for proper adhesion prior to painting. (extra attention)

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws or hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

Front Entrance

Air Lock - Paint all walls, accent back wall.

Cafeteria – Ceiling and ductwork – Paint white. Sound panels to be removed and re-installed.

Stage Soffit – Paint black

Stage Front – Paint black

Stage Walls – Paint all walls.

Other sloped metal ceiling areas (blue) – Paint neutral

All other walls – Paint neutral

Small Dinning – Paint all walls.

Serving Line – Paint all walls, both sides of back wall.

Food Prep – Paint all walls.

Back Door and Ceiling include supports – Paint all per material type

Office – Paint all walls.

Hall to Gym – Paint all walls, accent columns.

GYM

Ceiling deck – Paint ceiling deck.

Ductwork – Paint, color change.

Sound Panels – Paint same as wall color.

Walls – Paint wanes coat, similar to existing, upper color neutral, lower ?

Office/restroom – Paint all walls, neutral

Student Restrooms – Paint all walls, neutral

Music Room – Paint walls, match existing accent color wall.

Media Center

All ductwork and ceiling including steel, paint white

All walls – Paint neutral. Paint back wall, accent color.

Media Production – Paint back wall green, all others neutral.

Conference Room – Paint all walls neutral.

Office – Paint all walls neutral

Reading space – Paint all walls neutral, accent columns.

Group Toilets

Ceilings – Paint white

Column corner to column corner, paint accent color. Hallway stripe to continue to inside restroom corner.

Single Toilet (staff and classrooms) – Paint all walls, neutral.

Hallways – Paint all walls, paint stripe at top of walls, both sides, 1 block off ceiling. Match where condition is unusual. End walls neutral. Eliminate wanes coat in hallways. Paint ban through classroom insets. Accent hallway bulkhead, all sides. Accent classroom insets, block to block.

Upstairs Hallway Intersection (windows to cafeteria and media center – Paint all walls neutral, accent window wall to cafeteria. Paint full block stripe throughout area.

Kindergarten Hall – Cover mural, hall of fame lettering.

All Classrooms – Paint all walls, accent wall opposite door.

All offices – Paint all walls, accent wall opposite door.

Upstairs Asst. Principal Office – Protect Mural

Paint all walls, accent wall opposite door.

Stairways

Walls, underside of stairs – Paint neutral, accent outside wall. Paint conduit in paint area.

Rails and stair stringers – Paint black.

Administration Area

Entry Area – Paint all walls neutral, match accented areas with accent color.

Reception - Paint all walls, neutral, extend accented to corner.

Conference Room – Paint all walls, accent wall opposite door.

Health Room – Paint all walls, accent fight corner from Admin. To corner before shower door.

Principal Office – Paint all walls, color change on existing accent wall. Paint all others neutral.

EXTERIOR:

Doors on storage building (back near cafeteria entrance), both sides.

Downspouts Boots – Paint all around entire school.

Covered Play Area – Paint all ceiling deck and what is not blue. Paint sprinkler pipe and ceiling steel.

Mauldin High – Approximately 50,000 sq. ft.

All painting at this site is exterior except Student Entry Hall

Student entry hall – Paint over mural scene, match neutral color

Exterior Student Entrance – Paint ceiling entrance above doors

Paint all paintable exterior doors and exterior railing.

Gym Entry Exterior – Paint ceiling

Main Building – Paint all E.I.F.S. on front entrance and around main building.

Baseball buildings – Paint exterior of all buildings, color change. Cover script letters.

Football Press Box (2 story building) – Paint exterior and interior of building

Paint lower restrooms walls, doors and frames

Paint stair walls and steel on stairs to upstairs

Upstairs space, paint all walls, all stair steel.

Monarch Elementary – Approximately 107,396 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Prepare surfaces for proper adhesion prior to painting.

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

Atrium – Paint all walls to ceiling. Paint ceiling steel, color change. Bulkheads yellow to light blue, blue to different blue, paint columns neutral.

Restrooms – Paint all walls

Cafeteria

Cafeteria – Paint all walls

Teacher Dining – Paint all walls

Stage – Paint all walls black and stage front black.

Rails – Paint all rails on steps and ramp, match color.

Serving Line – Paint all walls, accent back serving wall, both sides.

Food Prep Area – Paint all walls.

Paint all walls in Office, Locker Room and Restroom.

Plant Engineer Office and Break Room – Paint all walls.

Gym

Paint all walls to ceiling (remove and replace sound panels)

Restrooms (2), Office and Office Restroom – Paint all walls

Cafeteria Hallway – Paint walls to ceiling same as Atrium.

Computer Lab – Paint all walls

Media Center – Paint all walls and ceiling

Reading Area - Paint all walls, match soffits and columns

Media Production Room – Paint entire wall for green media production color.

Faculty Lounge – Project Mural wall and sink wall.

Faculty restroom walls – Paint to match.

Classroom Hall – Paint all walls neutral. Paint accents, water cooler back wall. Intersection bulkheads, paint to match existing.

Group Restroom – Paint all walls, match colors

All Single Toilets (Staff and classrooms) – Paint all walls

Room 214 – Paint all walls, accent wall opposite door.

Room 313 Asst. Principal – Paint all walls, accent cabinet wall.

Nurse Area – Paint all walls, red to krypton, blue to dark blue, others neutral, restrooms all neutral.

Administration Area

Principal Office - Paint all walls, match accent.

Hallway – Paint all walls, eliminate yellow.

Secretary Office – Paint all walls, accent to new blue.

Entrance Lobby – Paint all walls,

Clerk Area window wall, blue, corner to corner. All other walls neutral

EXTERIOR:

Paint all ceiling E.I.F.S. around entire building, color change.

Paint all columns around entire building.

Covered Playground – Paint ceiling E.I.F.S.

Paint all exterior doorway and window lintels.

Monaview Elementary – Approximately 92,519 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Paint all handrails, interior and exterior. Prepare surfaces for proper adhesion prior to painting.

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws or hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

Atrium – Paint Steel Red

Paint sound panels neutral

Paint lower Drywall blue, vertical and horizontal.

Paint upper drywall same as above.

Paint walls neutral

Paint ceiling drywall yellow and ceiling white.

Kindergarten Hall

Paint all wall neutral, accent all walls behind water cooler

Stairways (6)

Paint all walls, underside of stairs. Color change on accent walls. Paint stair stringers and rails.

Science Room – Paint all walls, color change on accent wall.

Room 720 – Paint all walls, color change

Cafeteria

Stage front – Paint black

Back stage walls – Paint to match existing

Paint serving line wall neutral. Eliminate stripes throughout.

End Walls and center soffit (vertical and horizontal), accent. Ceiling soffit, paint white.

Paint all railing to match existing.

Serving Line – Paint wall neutral, accent back wall, both sides.

Food Prep Area – Paint all walls neutral

Office – Paint all walls, krypton

Dish Return – Paint all walls, neutral

Back Door – Prep and paint both sides.

Cafeteria Hall – Match colors and pattern to atrium colors.

Plant Engineer Office Area – Prep and Paint all door and window frames. DO NOT PAINT WALLS.

Gym

Stage – Paint end walls and rails, skip sides (orange)

Restrooms – Paint all walls

Office/Restroom – Paint all walls and shelf wall. Repair cracks.

Ceiling – Proper preparation of all surfaces

Paint steel, ductwork and deck.

Walls – Protect murals except where noted.

Paint all walls and sound panels, krypton.

Paint line below sound panels, horizontally and vertical line next to lions.

Media Center – Paint all walls

Story Area – Paint ceiling steel red, paint other surfaces krypton.

Office – Paint all wall neutral

Media Production Room – Paint green screen back wall, paint all others neutral.

Conference – Paint all walls neutral.

Wall between 903 & 905 to corner neutral, cover mural.

Art Room – Paint all walls, accent wall to krypton

Classrooms – Paint all walls, accent color change

1st Grade Classrooms – Staff to tape murals, Paint all walls

Stairway – 17 door, protect mural, paint over tick marks.

2nd Floor Hallways

Room 303 and 305 Hall, paint over palm trees. Paint all walls

Room 306 Hall – Paint all walls, existing blue to Krypton. Color change green and orange to white duck.

Room 514 Hall - Paint all walls, green to krypton to water fountain as.

Room 510 Hall – Paint all walls krypton.

Room 507 Hall – Paint accent krypton, water fountain.

All Single Restrooms – Paint all walls one color, neutral.

All Group Restrooms - Paint all ceilings white. Paint common wall blue outside corner to inside corner.

Paint fixture wall krypton, paint all others neutral.

Room 403 – Paint doors and frames, skip walls.

Room 406 – Paint all walls, Red to Krypton in time out room.

Room 401 & 415 – Paint all walls neutral, Krypton accent.

Room 514 – Skip

Guidance Area – Paint all walls neutral, in room 704 and 706, accent to krypton.

Room 708 – Paint all walls krypton.

Hallway yellow to be matched.

Front Entry and Reception – Paint back reception wall and partition wall Mona Blue., paint all others neutral.

Health Room Area – Paint all walls, cot to office corner krypton. Restrooms all walls neutral.

Public Front Toilet – Pant common wall, match color. Paint accent on fixture wall krypton. Paint all other neutral.

Paint ceilings white

Administration Area – Paint all walls in offices and hallways. Paint all walls in restrooms.

Room 713 – Paint existing accent krypton, paint all others neural.

Room 715 – Paint existing accent wall yellow, paint all others krypton.

Exterior – Paint all rails interior and exterior.

Oakview Elementary – Approximately 114,993 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Paint all handrails, interior and exterior. **Prepare surfaces for proper adhesion prior to painting. (extra attention)**

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws or hanging equipment.

Protect all murals unless otherwise noted.

Protect all prometean boards and parts. **(Do Not Disassemble any parts)**

All walls to be painted throughout school as noted below:

Entrance Lobby

Cafeteria

Paint ceiling soffit horizontal white.

? Bulkhead

Serving line Paint all walls.

Food Prep Area – Paint all walls

Office – Paint all walls.

Dressing Room and Restrooms

Dish Return

Food Prep Area

Back Door and roll up door – Special attention to preparation.

Building Service/Plant Engineering Area – Paint all walls

Teacher Dining Hall Area – Paint all walls in hall, cover existing accent wall.

Dining Room – Paint all walls neutral, color change on accent wall

Gym

Walls – Paint Teal, color change to blustery sky. Red, color change to debonair. All others neutral.

Ceiling and deck to white.

Ductwork – Paint black.

Restrooms, Office and office restroom – Paint all walls

Sink counters – Paint with epoxy paint.

Music Room – Paint accent wall, others neutral

Skip Ramp Area

Shelving Area – Paint wall through shelves neutral

Assistant Admin Office – Paint all walls, accent wall opposite door.

SRO Office - Paint all walls, accent opposite door.

? Science Hall 513 – Green screen to ceiling, 1 block wider.

Classroom Hallways – Paint all walls in all halls.

Grade Hallways – Paint accent beams and door insets

All Classrooms – Paint all walls, accent teacher wall.

Lower grade (K – 3rd) classrooms – Paint single restrooms and conference/office walls neutral.

Cross Hall Teacher work room – Paint all walls, accent small wall across from door.

Group Toilets – Paint all walls, accent entry front wall inside corner around to inside corner.

Single Toilets throughout school – Paint all walls, neutral.

Media Center – Protect Murals

Reading Area - Paint all walls

Media Production – Paint 2 walls green screen corner to corner.

Office – Paint all walls

Conference Room – Paint all walls, neutral

Non-Mural Walls – color change

Administration Area – Paint all walls in hallways and offices. Accent office walls across from door.

Office Entry Area – Paint all walls neutral, accent both sides of counter wall drywall.

Reception Area – Paint all walls, back wall, color change.

Conference Room – Paint all walls neutral, accent left and door wall.

Main Door – Paint to match standard door color.

Work Room – Accent counter wall

Health Room Area – Paint all walls neutral, accent cot wall, corner to corner.

Restrooms – Paint all walls.

Principal Office – Paint all walls neutral, accent existing accent wall.

Secretary Office – Paint all walls, accent door wall.

Cross Hall – Paint all walls, neutral. ? accent bench wall inside corner to inside corner.

Office Restrooms – Paint all wall one color.

Paris Elementary Approximately 72,200 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Paint all handrails, interior and exterior. Prepare surfaces for proper adhesion prior to painting. (extra attention)

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws or hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

Atrium

Red steel to handrail color

Top Bulkhead – Paint all white.

Both bulkheads – Paint same color

Walls – Paint neutral

Back and Front Hall ductwork – Paint white.

Back Hall – Paint same as entry atrium.

Cafeteria

Stage Front – Paint black.

Stage Walls and ramp walls – Paint all walls

Stair and ramp rails – Paint all.

Eating Area – Center ceiling, paint 3 sides of bulkhead accent, center ceiling white.

Serving Line – Paint all walls neutral, accent back wall, both sides. Back wall to dish return corner.

Food Prep Area – Paint all walls.

Office – Paint all walls.

Back door and outside ceiling area – Paint both sides of door and exterior ceiling.

Teacher Dining – Paint all walls, accent board wall.

Gym

Ceiling deck and steel - Paint white, including conduit.

Ductwork – Paint all to wall

Walls – Paint all to ceiling, match existing. Accent new color.

Office/restroom and student restrooms – Paint all one color.

Custodial Office/Receiving Area – Paint all walls, 1 color.

Media Center

Office Walls – Paint all walls

Story Area – Paint 3 sides of ceiling bulkhead. Paint walls neutral

Paint red steel, cc. Yellow to Krypton.

All other media center walls – Paint neutral

Ceiling and sprinkler pipe – Paint white

Media Production Room – Paint whole wall green screen walls, paint other neutral.

Conference Room – Paint all walls neutral

Entry bulkhead – Paint all faces accent

Room 720 work room – Paint all walls, neutral

All single toilets – Paint all walls, neutral

All Group Toilets – Paint all ceilings white. Paint all walls neutral. Paint accent entry wall around to other side inside corner.

Science Room – Paint all walls, accent wall opposite door.

Room 725 – Paint left wall, color change. Paint other walls neutral.

Hallway Walls – Paint all walls in all hallways, neutral

Hallway intersection and end of hall bulkheads – Paint accent (3 sides)

All Classrooms – Paint all walls, accent teaching wall.

Kindergarten rooms and restroom – Paint all walls neutral, paint accent, teaching wall.

Stairways (6) – Paint stringer, rails and risers, color change.

Paint all walls to ceiling, paint accent on exterior wall (up and down), include column and pipes.

Room 103 – Do not paint

UPSTAIRS

Halls and Restrooms – Paint all walls

Art Room – Paint all walls, accent teaching wall. **Paint over mural.**

Music Room – Paint all walls

Rooms 907, 908 and 909 – Paint all walls, accent teacher wall.

Room 902 – Paint all walls, accent wall opposite door.

Entry Group Toilet – Paint ceiling, white and all walls neutral.

Health Room – Paint all walls. Accent pack cot wall and left side.

Paint all other walls neutral include office and restrooms.

Guidance Area – Paint waiting area walls, accent interior right to next exit corner.

Paint all office walls, accent wall opposite door

Administration Area

Principal Office – Paint all walls, accent exterior wall.

Work Room – Paint all walls, accent wall opposite door.

Conference Room – Paint all walls, accent same accent wall, color change.

Restrooms – Paint all walls, color change.

Literary Specialist – Paint all walls, accent opposite main hall door wall.

Reception/Entrance lobby Area – Paint all walls neutral, accent back reception wall and counter wall.
Paint bulkhead neutral.

EXTERIOR

Front entry ceilings – Paint white

Side entry ceilings – Paint white

All Black Railing – Paint black.

Robert Cashion Elementary Approximately 101,378 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Paint all handrails, interior and exterior. Prepare surfaces for proper adhesion prior to painting. (extra attention)

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws or hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

New Additions (4th and 2nd grade halls) – Paint horizontal portion of soffits in hallway intersections

OLDER SECTION OF BUILDING.

Atrium

Ductwork – Paint all ductwork, color change.

Soffits – Paint all soffits, color change.

Ceiling Steel – Paint all steel, color change.

Columns – Paint all columns, color change.

Walls – Paint all walls neural.

Media Center – **cover all murals**

Paint all walls, cover all murals.

Ceilings – Paint paintable all ceilings white.

Columns and soffits (all sides) – Paint all accent, color change.

Media Production Room – Paint all walls, paint green screen, **cover mural.**

Offices – Paint all walls, eliminate accent walls.

Hallways – Cover Murals

Paint all walls in all halls. Paint accent band at top of wall, 1 block high. Varied colors.

Hall intersections – Paint all soffits

Hall outside cafeteria – Protect mural at bench. Paint bench and wall under bench black.

Cafeteria

Stage Area – Protect Stage Mural. Paint stage front black. Paint all other walls neutral.

Ramp, Ramp rails and stair rail – Paint to match

Paint all walls, neutral

Ceiling Soffits – Accent 3 sides, ceiling white.

Serving Line – Paint all walls, accent back wall (both sides). Continue accent to corner of tray drop corner.

Dish Return – Paint all walls

Office – Paint all walls

Locker Room/Restroom – Paint all walls.

Back Door and Dock Ceiling – Paint both sides of door and dock ceiling.

Gym- Protect Red Conduit (fire)

Ceiling - Paint ceiling, white

Ductwork – Paint all ductwork include square at wall, color change.

Walls - Paint all walls to ceiling.

Office/Restroom – Paint all walls.

Student restrooms – Paint all walls.

Classrooms

Paint all walls in all classrooms.

Kindergarten Classroom Conference Rooms – Paint all walls in workroom area.

Group Restrooms – Paint all walls. Accent entrance wall corner around to inside corner.

Ceilings – Paint all ceilings.

Single Toilets (Staff and Classrooms) – Paint all walls, neutral.

Main Lobby Restroom – Paint all walls, accent entry wall around to inside corner sink wall. Do not accent back wall.

Health Room – Paint all walls, accent cot wall. Paint restroom walls.

Administration

Principal – Paint all walls, accent existing wall, color change.

Entry Lobby – Paint all walls include counter wall, both sides of counter wall.

Receptionist Area – Paint all walls, accent back wall

All Individual Offices – Paint all walls, accent existing accent wall, color change.

Restrooms – Paint all walls neutral.

Teacher Workroom – Paint all walls, accent cabinet wall.

Old Conference Room (now office) – Paint all walls, accent wall adjacent to main corridor.

Hallway – Paint all walls, accent wall that contains work room door from corner of guidance offices around to corner of back door to hallway.

EXTERIOR

Exterior doorway ceilings – Paint all doorway ceilings.

Sterling School/Townes Gifted Center Approximately 132,505 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Paint all handrails, interior and exterior. Prepare surfaces for proper adhesion prior to painting. (extra attention)

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws or hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

Cafeteria

Seating Area – Paint all walls. Paint accent on all sides of ceiling soffit.

Serving Line – Paint all walls, accent both sides of back serving line wall.

Food Prep Area- Paint all walls

Dish, Return Paint all walls

Receiving Dock – Paint ceiling of dock area. (Protect Sprinklers)

Bollards – Paint traffic yellow.

Stairways (4) – Paint all Rails, stringers, underside of stairs, ceilings and riser pipe. (repair column cracks)

All Group Toilets - Paint all walls and ceilings, accent entry wall, inside corner around to inside corner.

Paint sink supports and tops, wall color (concrete paint)

All single toilets throughout school (classrooms, staff, etc.)

All Hallways – Paint all walls, accent water fountain walls. Add strip top block to soffits. Paint accent all sides of ceiling soffits.

Main Hallway (outside Cafeteria) – Paint all walls, accent high window insides.

Humanity Hall – Protect all murals

Music Room – Paint all walls to ceiling

Connector Hall – Paint walls

Chorus Room – Paint all walls

Practice Rooms – Paint all walls

Art Rooms – Paint all walls in two classrooms

Do Not Paint Connector Space

Education Halls (classrooms) – Paint all walls in all classrooms, accent existing accent wall, cc

Hall outside custodial room 510 – Paint all walls, cover murals

Gym – Paint all walls to ceiling

Ceiling – Paint deck and ductwork to match

Hallway – Paint all hall walls.

Stage – Paint back wall and ceiling black.

Stage walls and ramp walls – Paint to match.

Paint Rails

Locker Rooms (2) – Paint all walls and counter tops (concrete)

Shower Stalls – Paint all walls

Benches – Paint all benches.

Offices (2) and restrooms – Paint all walls

Laundry Room – Paint all walls.

Media Center

High Ceiling – Paint white

All Ceiling Drywall – Paint one color

Side Walls – Paint all walls

Entrance Walls – Paint all walls

Conference Room – Paint all walls

Media Production Room – Back wall, paint existing line to ceiling. 7-1/2" ceiling tile left.

Guidance Area

Paint all walls, paint existing accents as directed

Paint hall walls door conger right to office door corner

Health Room – Paint back wall, krypton

Restroom walls to neutral

Administration Area

Offices – Paint all walls neutral, accent existing accent to Krypton

Entry Lobby – Paint all walls

Receptionist Area – Pall walls

Halls – Accent corner net to restroom to door corner (interior wall).

EXTERIOR

Door Window Lintels – Paint all on exterior.

Downspout Boots – Paint all around exterior

Covered kindergarten play area – Paint ceiling.

Tigerville Elementary – Approximately 65,656 sq. ft.

Color selections and more detailed drawing will be provided once Contractor is identified.

Paint all paintable doors, frames, storefronts and mullion, both sides, throughout school. Paint all handrails, interior and exterior. Prepare surfaces for proper adhesion prior to painting. (extra attention)

Repair all pre-cast joints, minor block joints and sheetrock cracks within painted areas. Patch all holes without screws or hanging equipment.

Protect all murals unless otherwise noted.

Protect all promethean boards and parts. (Do Not Disassemble any parts)

All walls to be painted throughout school as noted below:

Front Entrance Area and Front Lobby – Paint all walls. Paint bulkheads, all side, accent. Paint curved bulkhead white. Paint columns neutral.

Wall with grills, paint red include red for grills(metal).

Cafeteria

Ceilings and ductwork – Paint white. Ductwork metal paint.

Seating area – Paint all walls.

Stage – Paint all walls, paint stage front black

Serving Line – Paint all walls, accent back wall both sides, **eliminate stripe, paint over.**

Food Prep Area – Paint all walls

Office – Paint all walls

Dish Return – Paint all walls

Locker Room and restroom – Paint all walls

Teacher Dining – Paint all walls, accent existing accent, color change.

Back Door – Prep and paint both sides.

Outside Ceiling – Paint all ceiling area.

Gym

Walls - Wanes Coat, color change 6 block blue. 1 block green, remaining wall to ceiling, neutral including sound panels. Accent glass block wall. Paint over any conduit within painted area.

Ceiling deck, steel and duct, include square duct, paint

Restrooms, Office and restroom – Paint all walls.

Media Center

Clearstory Area Ceiling – Paint white

All Walls in Clearstory – Paint accent color.

Glass block wall – Paint accent, stop at corner.

Reading Area – Paint all walls, neutral

Ceiling Area – Paint all white.

Media Production Room – Paint all walls neutral, protect mural

Conference Room

Ceiling bulkheads – Paint all sides

Walls – Paint all walls, accent wall opposite hall door.

Computer Room – Paint all walls, accent teaching wall and wall opposite hall door.

Group Toilets – Paint all walls, accent entry wall around to inside corner, male and female sides.

Entry bulkheads – Paint all sides. Paint strip continue from hall to restroom.

Single Toilets (staff and classroom toilets) – Paint all walls.

Hallways – Paint all walls. Paint stripe at top, similar to existing.

Paint all sides of intersection bulkheads, all sides. Paint ceilings white where exist.

All Classrooms – Paint all walls in classroom, accent 2 walls, teaching wall and exterior wall.

Science and Art Rooms – Paint all walls, accent same as classroom walls.

Music Room – Paint all walls, accent outside wall and wall opposite door.

Public Restroom – Paint all walls, accent behind door to corner by sink. Paint sink supports.

Guidance Area

Waiting Area – Paint all walls

Office – Paint all walls, accent window wall in each office

Conference Room – Paint all walls, accent hall wall

Teacher’s Lounge – Paint all walls, accent wall, color change.

PTA – Paint all walls, one color

Room C106 & C107 – Skip

Room C111 – Paint all walls.

Administration Area

Principal Office – Paint all walls, match current accent wall.

Hall Walls – Paint all walls, accent through window wall.

Entry Lobby – Paint all walls

Reception – Paint all walls, accent color change.

Secretary Office – Paint all walls, accent color change.

Restrooms (2) – Paint all walls

Work Room – Paint all walls, accent color change.

Health Room – Paint all walls. Paint accent to wall between restrooms

Restrooms – Paint all walls in restroom, one color.

Exterior:

Covered Kindergarten Play Area – Paint Ceiling

Paint all Lintels over windows and doors

Downspout Boots - Paint all steel downspout boots.

Front entry porch ceiling – Paint white.