



Procurement Department

2 Space Drive • Taylors, SC 29687-6072 • (864) 355-1279 •

The School District of Greenville County

Addendum No. 1

Date: **May 11, 2023**

Re: **Blue Ridge Middle – ADA Accessible Security Vestibule**

IFB No.: **323-32-5-23**

The following information becomes part and parcel of Invitation for Bid (IFB) #323-32-5-23 effective this date. Firms must acknowledge receipt of this addendum in their solicitation response.

The listed items add to, modify, or otherwise alter the specifications and become part of the solicitation documents. Where a portion of the original specifications are added to, modified, or also altered, the portion not so affected shall remain. Firms may have the right to protest this addendum.

Additional Documentation:

In addition to this addendum, documents referenced in this addendum have been provided and may be found on The School District of Greenville County's website at the link below:

<<https://www.greenville.k12.sc.us/Departments/main.asp?titleid=solicitations>>

- Updated electrical site drawing "E201revA"
- Supplemental drawing "2023.05.11 BRMS Summer Access Diagram Updated"
- Walk-off carpet in the new airlock - Specifications

Inquiries/ District Responses

Before the solicitation inquiry deadline, the District received an inquiry regarding this solicitation. The District's response to the question follows in **bold** font.

1.) Please confirm the site lights shown on E 201 should be included in the Alternate and not the Base Bid. **"LP2" lights (and all Note 11 requirements) shall be included in Alternate One pricing.**

2.) Please confirm if a floor covering and rubber base are required for the new secure entry. **Walk-off carpet is required in the new airlock. The specification information has been provided and on the Procurement Department website. See section above regarding "Additional Documentation". Rubber base shall be installed - color to match existing. Gypsum board walls to be painted - color to match existing office color. Exterior brick shall blend with existing – submit color samples for review prior to ordering.**

3.) Please confirm access control hardware is not a requirement for the new secure vestibule door. **Existing access control devices should be protected and remain in service.**

4.) Please confirm manufacturer of the existing fire alarm system.

Secutron 2400 fire panel.

See below for two supplemental notes for handrails:

1. Cope components at connections to provide close fit, welding all around, or use fittings designed for this purpose.
2. Welded joints in handrails shall be completely sanded smooth IAW NOMMA's "Voluntary Joint Finish Standards" for Type 2 welds.

End of Section – Inquiries/District Responses

All other terms and conditions remain unchanged and in force.

Thank you for your interest in the District.

Tonya A. Stroud

Tonya A. Stroud
Senior Buyer