

Addendum No. 2

Date: **July 24, 2024**

Re: **Exterior Wall and Sealant Repair - Grove Elementary**

IFB No.: **324-152-8-7**

The following information becomes part and parcel of **Invitation for Bid (IFB) #324-152-8-7** effective this date. Firms must acknowledge receipt of this addendum in their solicitation response.

The listed items add to, modify, or otherwise alter the specifications and become part of the solicitation documents. Where a portion of the original specifications are added to, modified, or also altered, the portion not so affected shall remain. Firms may have the right to protest this addendum.

An additional inquiry was received by the District that requires a District response for clarification purposes. Please see the inquiry, and the District's response, below:

1.) We had some questions regarding the helical piles. Drawing C-2, notes 1-5 indicate that each helical is to be used to lift the structure or put a preload onto the helical piles. Could you clarify if this is the case or if the owner would prefer to underpin/stabilize without loading the piles? If they do intend on loading the piles, is there a specification on how much (pressure, vertical footing displacement, etc.)? I have not seen this in the specifications, but I have not fully gone through them yet. Are there any other load requirements other than note 4 on sheet C-2 (Each helical pier shall be able to support a minimum of 12kips)?

The primary goal is to stabilize the wall. Each pier will need to be able to support 12 Kips. The secondary goal is to apply pressure on the foundation to lift the wall a small amount. This is going to be one of the items we monitor in the field. We do not anticipate lifting the wall much. Moving the wall quickly is not the goal here, the wall will continue to move over the next month or two.

End of Section

All other terms and conditions remain unchanged and in force. Thank you for your interest in the District.

Tonya A. Stroud

Tonya A. Stroud
Senior Buyer